CITY OF PRESCOTT
ARIZONA
Everybody's Hometown

Mark Nietupski, Public Works Director

433 N. Virginia Street
Prescott AZ 86301
928-777-1130

ADDENDUM NUMBER ONE
to the
PROJECT SPECIFICATIONS
and
CONTRACT DOCUMENTS
for
FY 2014 Pavement Preservation Project

DATE OF ADDENDUM: **March 25, 2014**

BID OPENING DATE: **April 3, 2014** (unchanged)

TO ALL BIDDERS BIDDING ON THE ABOVE PROJECT:

The following addendum shall be made part of the Contract Documents. All other provisions of the Contract Documents remain unchanged. The Bidder shall acknowledge receipt of this addendum on page 15 of the Proposal by inserting the addendum number and date on the executed page of the Proposal. The contents of this Addendum shall be given full consideration in the preparation of the Bid.

CLARIFICATIONS:

Section 331 – Microsurfacing in the Special Provisions is supplemented as follows:

Minimum Sampling and Testing Frequency:

Fine Aggregate Gradation: Sample fine aggregate from the project stockpile and test for gradation and sand equivalency. As a minimum perform one test per 500 tons of fine aggregate.

Asphalt Content: Calculate the percent asphalt content of the mixture at least three times per day. The Owner's on-site representative shall randomly determine the timing for the readings used to calculate asphalt content.

Application Rate: Calculate the yield of the course placed at least three times per day. The Owner's on-site representative shall randomly determine the timing for the readings used to calculate application rate.

Documentation: Complete a daily report that includes the following information:

Job number
Route/Street Name(s)
Owner's On-Site Representative
Date
Air temperature – Min/Max (during application)

Unit Weight of emulsion (pounds per gallon)
Beginning and ending application locations
Counter readings (beginning, ending, and total difference)
Total area (square yards)
Aggregate weight
Gallons of Emulsion
Application rate (pounds per square yard)
Contractor's authorized signature
QC aggregate properties (if required)
Asphalt emulsion bill(s) of lading

Acceptance: Allow the Engineer access to in-progress work for quality assurance review and testing.

Crack Repairs:

Crack Repairs at the Prescott Municipal Airport are deleted from the work. The following Bid Items are deleted from the Bid Schedule:

337a – Crack Repair Detail "A"
337b – Crack Repair Detail "B"

Delete: Bid Schedule
Add: Revised Bid Schedule (attached)

- END -

City of Prescott, Public Works Department

Mark Nietupski, Public Works Director

3/25/14
Date

Acknowledgement: (**must** be signed and turned in with the bid documents)

Company Name

Date

Signature of Company Official

REVISED BID SCHEDULE

FY 2014 PAVEMENT PRESERVATION PROJECT

Item	Description	Quantity	Unit	Unit Cost	Amount
	City Streets				
100.4	Public Relations Allowance	1	LS	$16,000.00	$16,000.00
104.3	Mobilization	1	LS		
105.8	Construction Staking	1	LS		
109.1	Contract Allowance	1	LS	$80,000.00	$80,000.00
331.8a	Microsurfacing Dry Aggregate	2,300	TN		
331.8b	Microsurfacing Asphalt Emulsion	300	TN		
332.9a	Asphalt Emulsion Slurry Seal Coat	82,000	SY		
345.1a	Adjust Sewer Manhole Frame and Cover	34	EA		
345.1b	Adjust Storm Drain Manhole Frame and Cover	17	EA		
345.1c	Adjust Water Valve Box and Cover	74	EA		
401.7a	Traffic Control Plan	1	LS		
401.7b	Flaggers	940	HR		
401.7c	Certified Police Personnel Allowance	1	LS		
401.7d	Barricades and Storage	1	LS		
401.7e	Lighted Message Board	40	Day		
401.7f	Incidental Traffic Control Related Items	1	LS		
402.1a	Obliterate Existing Thermoplastic Striping	16,000	LF		
402.1b	Obliterate Existing Thermoplastic Left Arrow	35	EA		
402.1c	Obliterate Existing Thermoplastic Right Arrow	24	EA		
402.1d	Obliterate Existing Thermoplastic Thru Arrow	4	EA		
402.1e	Obliterate Existing Thermoplastic Right/Thru Arrow	3	EA		
402.1f	Obliterate Existing Thermoplastic Left/Thru Arrow	7	EA		
402.1g	Obliterate Existing Thermoplastic Merge Arrow	10	EA		
402.2a	Thermoplastic Striping - Yellow	930	LF		
402.2b	Thermoplastic Striping - White	15,000	LF		
402.2c	Thermoplastic Striping - Left Arrow	35	EA		
402.2d	Thermoplastic Striping - Right Arrow	24	EA		
402.2e	Thermoplastic Striping - Thru Arrow	4	EA		
402.2f	Thermoplastic Striping - Right/Thru Arrow	3	EA		
402.2g	Thermoplastic Striping - Left/Thru Arrow	7	EA		
402.2h	Thermoplastic Striping - Merge Arrow	3	EA		
402.3a	Temporary Striping - Yellow Paint	78,000	LF		
402.3b	Temporary Striping - White Paint	140,000	LF		
402.3c	Temporary Striping - Left Arrow	35	EA		
402.3d	Temporary Striping - Right Arrow	24	EA		
402.3e	Temporary Striping - Thru Arrow	2	EA		
402.3f	Temporary Striping - Right/Thru Arrow	3	EA		
402.3g	Temporary Striping - Left/Thru Arrow	7	EA		
402.3h	Temporary Striping - Merge Arrow	10	EA		
402.4a	Permanent Striping - Yellow Paint	122,000	LF		
402.4b	Permanent Striping - White Paint	63,000	LF		
405.3.2	Adjust Survey Monument Frame and Cover	23	EA		
505.1d	Catch Basin No. 1	1	EA		
505.1e	Catch Basin No. 2	1	EA		

REVISED BID SCHEDULE

FY 2014 PAVEMENT PRESERVATION PROJECT

Item	Description	Quantity	Unit	Unit Cost	Amount
601.2.11	Rock Removal (Trench) - Provisionary Item, May Not Be Used	10	CY		
738	18" HDPE Storm Drain Pipe	20	LF		
	SUBTOTAL - CITY STREETS				
	Prescott Municipal Airport				
104.3	Mobilization	1	LS		
109.1	Contract Allowance	1	LS	$10,000.00	$10,000.00
332.9b	Asphalt Emulsion Slurry Seal Coat - Administration Parking Lot	6,200	SY		
332.9c	Asphalt Emulsion Slurry Seal Coat - Bottleneck Ramp	30,000	SY		
333.10	Fog Seal Coat	39,000	SY		
401.7a	Traffic Control Plan	1	LS		
401.7b	Flaggers	30	HR		
401.7d	Barricades and Storage	1	LS		
401.7f	Incidental Traffic Control Related Items	1	LS		
	Pavement Markings - Administration Parking Lot				
402.3a	Temporary Striping - Yellow Paint	100	LF		
402.3b	Temporary Striping - White Paint	1,800	LF		
402.4a	Permanent Striping - Yellow Paint	100	LF		
402.4b	Permanent Striping - White Paint	1,800	LF		
402.4e	Handicap Stall	4	EA		
	Pavement Markings - Bottleneck Ramp				
402.3k	Temporary Pavement Markings - Yellow Paint	4,100	SF		
402.3l	Temporary Pavement Markings - Black Paint	54	SF		
402.3m	Temporary Pavement Markings - Geographic Position Marking	1	EA		
402.4f	Permanent Pavement Markings - Yellow Paint	4,100	SF		
402.4g	Permanent Pavement Markings - Black Paint	54	SF		
402.4h	Permanent Pavement Markings - Geographic Position Marking	1	EA		
	SUBTOTAL - PRESCOTT MUNICIPAL AIRPORT				
	TOTAL BID AMOUNT				

Total Base Bid: (Not Including Bid Alternates)

_____ Dollars

(Written Words)

_____ _____

Signature of Company Official — Title

_____ _____

Company Name — Phone Number

_____ _____

Address — Fax Number

_____ _____

City/State — Zip Code