



**ADDENDUM NUMBER ONE  
to the  
PROJECT SPECIFICATIONS  
and  
CONTRACT DOCUMENTS  
for  
CIP 15-033 RODEO GROUNDS SEDIMENT CONTROL BASIN**

**DATE OF ADDENDUM:** February 12, 2016

**TO ALL BIDDERS BIDDING ON THE ABOVE PROJECT:**

The following addendum shall be made part of the Contract Documents. All other provisions of the Contract Documents remain unchanged.

**Add the following to the City of Prescott Project Specifications and Contract Documents Section 340.4.3 and 505.1.1.E:**

Concrete for new slabs and retaining wall shall be colored with a pigment incorporated integrally into the concrete mix prior to placement. Pigment material shall conform to MAG 725.5. Pigment color shall be tan or light brown subject to City approval of color. Proposed product information and color samples shall be submitted for review and approval by City prior to construction. Finishing and curing shall be in accordance with the pigment manufacturers recommendations. Colored concrete is not required for the modifications to the existing headwall.

All labor and materials required for color concrete shall be done incidental to the bid item.

**Revise Plan Sheet L.3, Figure 5:**

The spacing between vertical rails shall be 1 foot – 2 inches for a top rail height of 42-inches.

- END -

City of Prescott, Public Works Department

  
Henry Hash, Public Works Director 2-11-16

**Acknowledgement:** (must be signed and turned in with the bid documents)

\_\_\_\_\_ Company Name

\_\_\_\_\_ Date

\_\_\_\_\_ Signature of Company Official

\_\_\_\_\_ Date

## CLARIFICATIONS

1. I see a separate line item for grading on the bid schedule, # 215, and another item rock removal (Trenching) bid allowance, item # 601.2.11. I am not sure what the rock removal pertains to unless it is for unforeseen sub-surface rock in the swale area.

*The Bid Item 601.1.11 Rock Removal is only an allowance item to be approved by the City, should s bedrock layer be encounter within the graded area.*

2. In the pre-bid meeting, you had mentioned that there was not necessarily any SWPPP measures concerning this project, I saw a separate line item on bid sheet for SWPP measures, what would that pertain to?

*A storm water pollution prevention plan and Arizona Department of Environmental Quality Notice of Intent is not required for this project. SP 107.15 Storm Water Pollution Prevention Measures is the pay item for the installation of the sediment filter on the existing outlet structure; see Sediment Filter Detail on Page 3 of the Plans.*

2. Irrigation plan L2.1 does not specify that the two polyethylene tanks should be buried; I would assume so, but need clarification.

*The polyethylene tanks should be buried to reduce the visibility of the tanks. The City will determine the location of the tanks in the field for the contractor.*

4. Is the bid bond to be included at time of bid opening, or only after the project is awarded?

*The Bid Bond is due with the bid opening documents.*

5. Interpretive sign, mentioned on detail sheet, should that be included for installation with landscape bid?

*The interpretive sign will be installed by a separate contractor/contract.*