



ADDENDUM NUMBER ONE
for the
Transfer Station Slab Remediation Project

DATE OF ADDENDUM: June 10, 2016

TO ALL BIDDERS BIDDING ON THE ABOVE PROJECT:

The following addendum shall be made part of the Project Specifications and Contract Documents. All other provisions of the Contract Documents remain unchanged. The Bidder shall acknowledge receipt of this Addendum on page 15 of the Proposal, in addition to signing below and returning this form with the bid package. The contents of this Addendum shall be given full consideration in the preparation of the Bid.

CHANGES TO THE PROJECT SPECIFICATIONS:

Safety Net/Barrier-

Include: Contractor shall provide a safety net/barrier that spans the length of the pit opening from the lower wall to the building ceiling. The net/barrier is intended to protect workers, and finished work, while the transfer station is in operation. The net/barrier will be required during work on the cantilever on the side that is being repaired. Specific types of materials for the barrier will be determined by the contractor. The safety net/barrier shall be considered incidental to other items and no separate payment shall be made.

Transfer Station Existing Bollards and Footings-

Include: During the removal and reconstruction of concrete inside the transfer station the interior bollards within the reconstruction limits shall be removed. All concrete around the footings of the I-beams will be removed as well, leaving a minimum of 18" of existing rebar extruding from the footings. All other concrete material that surrounds the footing along the interior joints will be removed per specifications. New bollards shall be installed in the interior of the transfer station in similar locations as existing. The transfer station existing bollards and footings shall be considered incidental to other items and no separate payment shall be made.

- END -

City of Prescott, Public Works Department


Henry Hash, Public Works Director

6-10-16

Acknowledgement: (must be signed and turned in with the bid documents)

Company Name

Signature of Company Official

Date