



**Field and Facilities Services
2800 Sundog Ranch Road
Prescott, AZ 86301
Solicitation Amendment One**

Solicitation #/Name	Amendment #	Effective Date
IFB#FF2015-006	One (1)	04/10/2015

The above referenced contract is hereby modified as follows:

The following is the square footage of the five Fire Stations wall and ceiling areas.

- Station 71-10,246
- Station 72-9335
- Station 73-3,000
- Station 74-2,891
- Station 75-3,789

Total Sq. Footage=29,261

Questions:

1. We need to specify the type of epoxy we are bidding for the surfaces, the type of cleaning needed (TSP Wash), type of primer required.

All surfaces are to be cleaned with TSP per Manufactures recommendations.

2. Specifying a Manufacture like Sherwin Williams or Dunn Edwards is a good start.

Dunn Edwards will be the preferred manufacture specifications.

3. What painting process is required for current unpainted block walls - do we clean them, prime them and epoxy or do we add a block filler application for filling up the holes and voids?

All surfaces (including concrete block after B25W0002) get primer B49W00060.

4. Need to specify we are also painting the cabinet faces on station 74 as well as all unpainted shelving in the stations - Current painted cabinets stay as is.

Yes.

5. There is a lot of drywall repair to complete - please make sure that this is covered in the specifics

Repair all drywall holes as necessary to match existing finish.

6. Please have the contract read that we may apply for a draw after each fire station is completed.

Draws for payment will be based on completion and square footage of each station per the following percentages:

- *Station 71-35%*
- *Station 72-32%*
- *Station 73-10%*
- *Station 74-10%*
- *Station 75-13%*

Signature _____ Date _____

Except as provided for herein, all terms and conditions of the original solicitation not heretofore changed and/or modified remain unchanged and in full effect. In witness whereof the parties hereto sign their names in agreement.