CITY OF PRESCOTT
ARIZONA
Everybody's Hometown

Public Works Department

433 N. Virginia Street
Prescott AZ 86301
928-777-1130

ADDENDUM NUMBER THREE
to the
PROJECT SPECIFICATIONS
and
CONTRACT DOCUMENTS
for
Park Avenue Improvements Project
Project # 14-2157810-8930-09648

DATE OF ADDENDUM: **April 7, 2014**

BID OPENING: **April 10, 2014 (Unchanged)**

TO ALL BIDDERS BIDDING ON THE ABOVE PROJECT:

The following addendum shall be made part of the Contract Documents. All other provisions of the Contract Documents remain unchanged. The Bidder shall acknowledge receipt of this addendum on page 16 of the Proposal by inserting the addendum number and date on the executed page of the Proposal. The contents of this Addendum shall be given full consideration in the preparation of the Bid.

BID SCHEDULE:

Item 100.4 Public Relations Allowance – Unit Cost $40,000.00
Item 109.11 Contract Allowance – Unit Cost $400,000.00

DELETE: Revision II Bid Schedule

ADD: Revision III Bid Schedule (attached)

- END -

City of Prescott, Public Works Department

Scott Tkach 04-07-14
Scott Tkach, Interim Public Works Director

Acknowledgement: (**must** be signed and turned in with the bid documents)

_____ _____
Company Name Date

_____ _____
Signature of Company Official Date

PARK AVENUE IMPROVEMENTS
REVISION III BID SCHEDULE

Item	Description	Quantity	Unit	Unit Cost	Total Amount
100.4	Public Relations Allowance	1	LS	$ 40,000.00	$ 40,000.00
105.8	Construction Staking	1	LS		
107.15	Stormwater Pollution Prevention Plan (SWPPP)	1	LS		
109.10	Mobilization	1	LS		
109.11	Contract Allowance	1	LS	$ 400,000.00	$ 400,000.00
200.2	By-pass Pumping	1	LS		
205.1	Earthwork - Excavation & Embankment	8,197	CY		
205.2	Removal of Unsuitable Sub-Grade Material	2,500	CY		
207.2	Temporary Shoring	204	LF		
207.3	Temporary Traffic Barrier	224	LF/D		
211.6	Fill Construction	623	CY		
220.6	Grouted Rip Rap	6	CY		
301	Sub-Grade Preparation	19,911	SY		
306	Geogrid, Tensar BX-1100 with Class A Separation Fabric	3,600	SY		
310	Aggregate Base Course	4,653	CY		
317.2	Mill Asphalt Pavement - 2" Nominal Depth	1,925	SY		
317.2a	Mill Asphalt Pavement - 3" Nominal Depth	1,666	SY		
317.2b	Mill Asphalt Pavement - 4" Nominal Depth	2,056	SY		
317.2c	Mill Asphalt Pavement - 5" Nominal Depth	5,626	SY		
317.2d	Mill Asphalt Pavement - 10" Nominal Depth	5,795	SY		
321	Asphalt Concrete (AC) Pavement, 2" - 1/2" Aggregate	1,595	SY		
321a	Asphalt Concrete (AC) Pavement, 3" - 1/2" Aggregate	2,687	SY		
321b	Asphalt Conctete (AC) Pavement, 2" - 3/4" Aggregate	14,058	SY		
321.8.7	Pavement Fabric Interlayer	548	SY		
321.8.7a	Pavement Fabric Interlayer Binder Coat	137	GAL		
324	Concrete Driveway, 4"	561	SY		
324a	Stained/Colored Concrete Driveway, 4"	43	SY		
325	Asphalt Rubber Asphalt Concrete (ARAC) Pavement, 2" - 1/2" Aggregate	14,058	SY		
329	AC Bituminous Tack Coat, Type SS-1h	2	TON		
329a	Rubberized Asphalt Tack Coat, PG 64-16	4	TON		
336	Pavement Matching and Surfacing Replacement	640	SY		
340.4.1	Concrete Curb and Gutter, 6" Type A	9,681	LF		
340.4.2	Concrete Sidewalk	24,085	SF		
340.4.2.1	ADA Ramp	1,286	SF		
340.4.3	Concrete Driveway Entrance & 6" Concrete Slab	11,557	SF		
340.4.4	Concrete Valley Gutter	7,327	SF		
342	Concrete/Brick Paving Stone Driveway	60	SF		
345.3	Adjust Existing Frame and Cover	2	EA		
345.4	Adjust Existing Valve Box and Cover	1	EA		
345.4.1	Adjust Existing Meter Box	1	EA		
345.2.5	Adjust Existing Manhole	1	EA		
350.4.1	Removal and Abandonment of Storm Sewer (Non-Incidental)	1	LS		
350.6.1	Removal, Disposal, and Backfill of Non-Friable ACP	245	LF		
350.6.2	Removal, Disposal, and Backfill of Friable ACP	245	LF		
350.7	Remove Existing Signs	42	EA		
350.10	Removal of Vault and Tank (S Hassayampa)	1	LS		
401	Traffic Control Plan	1	LS		
401.2a	Barricades and Storage	1	LS		
401.2b	Message Boards (each per day)	1,200	DAYS		
401.2c	Incidental Traffic Related Items	1	LS		
401.3a	Flaggers	7,000	HR		
401.3b	Off Duty Police Officers	120	HR		

PARK AVENUE IMPROVEMENTS
REVISION III BID SCHEDULE

Item	Description	Quantity	Unit	Unit Cost	Total Amount
401.3c	Pilot Car and Driver (HR)	100	HR		
402.2a	Thermoplastic Striping, 12" Stop Bars, White	339	LF		
402.2b	Thermoplastic Striping, 18" Cross Walk, White	245	LF		
402.2c	Thermoplastic Striping, White 24" School Crosswalk	330	LF		
402.2d	Thermoplastic Striping, Right Turn Arrow, White	2	EA		
402.2e	Thermoplastic Striping, Combination Turn Arrow, White	2	EA		
402.2f	Thermoplastic Striping, School Legend, White	2	EA		
402.3a	Temporary Striping, Yellow	6,030	LF		
402.3b	Temporary Striping, White	800	LF		
402.4a	Permanent Striping, 4" Double Yellow	6,030	LF		
403.1a	Sign Posts	515	LF		
403.1b	Sign Panels	52	SF		
403.1c	Sign Post Foundation	42	EA		
405	Survey Monuments	44	EA		
430.1	Landscaping	1	LS		
430.3.2	Seeding, Hydraulic	0.21	ACRE		
431	Remove and Replace Landscape Rock	1	LS		
432	Landscaping Rock	2,556	SY		
434	Landscape Restoration	1	LS		
450	Antique Lighting	1	LS		
505	Concrete Wall, Detail 1, Sheet 7	28	LF		
505a	Concrete Wall, Detail 2, Sheet 7	9	LF		
505b	Concrete Wall, Detail 1, Sheet 22 (Provisional)	32	LF		
505.1.1A	3' x 3' Precast Concrete Juction Box	1	EA		
505.1.1A1	60" Precast Concrete Manhole and Base	5	EA		
505.1.1A2	6' x 8' Precast Concrete Junction Box	1	EA		
505.1.1B	Concrete Headwall	1	EA		
505.1.1C1	Curb Inlet with Catch Basin, 10' (9.67') MAG Type D, L= 6'	1	EA		
505.1.1C2	Curb Inlet with Catch Basin, 15' (13.5') MAG Type D, L= 10'	1	EA		
505.1.1C3	MAG Type E Catch Basin, Neenah R-3067-VB	2	EA		
505.1.1C4	MAG Type E Catch Basin, Neenah R-3295-2L	1	EA		
505.1.1C5	MAG Type F Catch Basin, 2' x 3' Precast, Neenah R-4843	1	EA		
505.1.1C6	North Hassayampa Outfall System	1	LS		
505.1.1D	Country Club Storm Drain System	1	LS		
505.1.1D1	Moreland Drive Storm Outfall System	1	LS		
505.1.1D2	Concrete Curb Outlet, Ellenwood	1	EA		
505.1.1D3	Curb Opening (Neenah R-3262-3)	5	EA		
505.1.1D4	510 Sierra Prieta Outfall System	1	LS		
505.1.1E	Concrete Retaining Wall, RW-1	2,218	SF		
505.1.1E1	Concrete Retaining Wall, RW-2	240	SF		
505.1.1E2	Concrete Retaining Wall, RW-3	1,648	SF		
520	Hand Rail, Sidewalk	24	LF		
601.2.11	Rock Removal (Trench)	7,139	CY		
605	6" Sch. 80 Non-Perforated PVC Drain Pipe	12	LF		
605a	6" Sch. 80 PVC Perforated Trench Drain Pipe	742	LF		
610a	4" DIP, Class 350 Water Main	152	LF		
610b	6" DIP, Class 350 Water Main	837	LF		
610c	8" DIP, Class 350 Water Main	3,113	LF		
610.1	Temporary Water	1	LS		
610.9	Fire Hydrant Assembly	6	EA		
610.9a	Reset Existing Hydrant	1	EA		
610.11.E	New 1" Copper Water Service And Reconnection	69	EA		

PARK AVENUE IMPROVEMENTS
REVISION III BID SCHEDULE

Item	Description	Quantity	Unit	Unit Cost	Total Amount
610.11.E1	New 2" Copper Water Service And Reconnection	1	EA		
610.11.G	Traffic Rated Concrete Meter Box	5	EA		
615	Sanitary Sewer Main - 8" PVC	4,182	LF		
615a	Sanitary Sewer Main - 8" DIP, Class 350	26	LF		
615.7	Sanitary Sewer Service, 4"	87	EA		
615.11.1	Mainline Closed Circuit Television	4,182	LF		
615.11.1a	Service Lateral Closed Circuit Television	87	EA		
618	8" C900 PVC Storm Pipe	72	LF		
618a	12" RGRCP	77	LF		
618b	18" RGRCP	79	LF		
618c	24" RGRCP	707	LF		
618d	36" RGRCP	36	LF		
625	48" Sanitary Manhole	21	EA		
625a	48" Sanitary Drop Manhole	7	EA		
625b	Internal Drop System	1	EA		
630.3a1	6" Gate Valve, box and Cover	14	EA		
630.3a2	6" InsertValve	1	EA		
630.3a3	8" Gate Valve, box and Cover	14	EA		
630.4	6" Tapping Sleeve, Valve, Box and Cover	1	EA		
630.6b	1" Combination Valve Assembly	2	EA		
630.6.1	Blowoff Assembly	1	EA		
650.1	Water Main Abandonment	1,975	LF		
650.2	Removal of Water Main	521	LF		
651.1	Abandonment of Sanitary Sewer	1,129	LF		
651.2	Removal of Sanitary Sewer	128	LF		
651.2a	Removal of Sanitary Manhole	1	EA		
701	Decomposed Granite, Driveways	22	SY		
701a	3/8" Washed Rock, Driveways	15	SY		
701b	1/2" Washed Rock, Driveways	19	SY		
701c	3/4" Washed Rock, Driveways	51	SY		
701d	3/4" Red Washed Rock, Driveways	50	SY		
043340	CMU Retaining Wall	376	SF		
	TOTAL BID:				

Total Base Bid

_____ Dollars

(Written Words)

_____ _____

Signature of Company Official Title

_____ _____

Company Name Phone Number

_____ _____

Address Fax Number

_____ _____

City/State Zip Code