



**CITY OF PRESCOTT
PUBLIC WORKS DEPARTMENT**

PROJECT UPDATE

Project Name:

Granite Creek Dam Valves Replacement Project

Date:

August 1, 2014

The Granite Creek Dam Valves Replacement Project generally consists of the replacement of two inoperable original large diameter valves (36", 48") at Granite Creek Dam constructed in 1919, and provide for operations of the valves from the dam crest via flexible operators. The proposed 36" replacement valve is to include a 12" bypass. The project also includes the replacement of existing upstream trash racks and installation of new slide gates.

Advertising for Statements of Qualifications to provide engineering design services commenced on 2/23/14. Stantec Consulting Services submitted their Statement of Qualifications on March 27, 2014. On April 28, 2014 Stantec made a presentation to staff on their qualifications and design approach to the project. A Scope and Fee Proposal has been solicited for consideration by staff.

**City Contact
Information
Project Manager:**

George Henderson 777-1130