



CIP 15-001 Lakeview Plaza Storm Drain Construction

The project was awarded to Earth Resources Corporation on May 26, 2015 with a notice to proceed given on May 27, 2015. The project includes installation of 420 feet of 48-inch Diameter Ultra Flo Storm Drain System from the Lakeview Plaza Development Drainage Vault across Willow Lake Road to an Outfall into Willow Creek. Additional work will include trenching rock removal, pavement surface replacement, removal and replacement of Reno Mattress, installation of new Reno Mattress, removal of steel grate, installation of aluminum hatch, construction of gabion headwall and other miscellaneous construction.

Background

During review of the Lakeview Plaza project, the benefit of jointly addressing drainage from the steep terrain above the development site impacting Willow Lake Road, and integrating flows from that property, was recognized. The new storm drain system is designed to prevent runoff from large storm events from adversely impacting Willow Lake and Willow Creek Roads in the immediate area. The project design was completed in-house by the Engineering Department staff.

Project Update

Earth Resources Corporation is currently installing the gabion baskets in Willow Creek below the storm drain outfall and the storm drain from Willow Lake Road section to Willow Creek. The project should be completed by the middle of July.



Questions concerning the project should be addressed to the Project Manager, Jeff Low at (928)777-1643 or emailed to jeff.low@prescott-az.gov.

Visit: www.prescottroadconstruction.com for additional project information.

City of Prescott • Public Works Dept. • 433 North Virginia Street • Prescott, Arizona 86301