



**CITY OF PRESCOTT  
PUBLIC WORKS DEPARTMENT**

**PROJECT UPDATE**

**Project Name:**

Small Water Mains Upgrades

**Date:**

AuguStreet20, 2010

Small Water Mains Upgrades: To meet the basic infrastructure needs of providing for safe, adequate drinking water for the City's residents and businesses, the City annually budgets funds for the replacement and upgrade of small, undersized and aging water mains. These mains are typically 3" or less in diameter, often constructed of galvanized steel and also a source of leaks. Replacement of these lines improves the water system for our citizens, helps to reduce maintenance costs, water loss and improves fire flow.

Flatau Drive, and Overstreet Drive, Leroux Street and Granite St: CLM Earthmovers is the contractor. Construction started on June 1, 2010 on Flatau Drive and Overstreet Drive. CLM is finished installing the water main on Flatau, Overstreet, South Granite Street, and South Granite Street West. The water service lines are active on Flatau, and Overstreet. The water main installation on Leroux is completed. Over the next week private water services will be tied into the new water main and sewer line backwater valves will be installed in parcels that front Leroux Street. Clean up and landscape restoration is on-going around all the construction areas. Rubber chip seal has been applied to Flatau and Overstreet.

Rodeo Grounds, Tolemac Drive to Wildwood Drive Connection and Ute Road: CLM Earthmovers is the contractor. Construction started on June 1<sup>st</sup>, 2010 on Ute Road. The water main has been installed in Ute and all water service lines have been tied over to the new water main. Construction began in the Rodeo Grounds July 12th. Most of the work to be performed in the Rodeo Grounds is finished. The new water main has been tied into the existing system, flushed and tested. Water services in the Rodeo Grounds will be tied over to the new water main this week. The connection line between Tolemac Drive and Wildwood Drive is active. Restoration and clean up will be done in the next two weeks.

**City Contact Information**

**Project Hotline Number: Ben Burns, 777-1130**