

ACKER PARK STORMWATER BASIN PROJECT

November, 2017

The stormwater detention basin has been constructed to detain 12 acre feet of storage during larger storm events, which will reduce flooding downstream of the basin. The construction project was completed by Fann Contracting. The constructed basin includes the basin spillway, gabion baskets at the basin inlet areas and below the spillway, three outlet structures (for different rainfall events) and landscaping composed of native drought tolerant plants, trees and native hydroseed. The project will be followed up by a new flood study for the Virginia Street Wash to remove several properties downstream of the project outside of the 100-year floodplain.



City Contact Information

Project Manager: Jeff Low 777-1643

Email: Jeff.Low@prescott-az.gov

Visit: www.prescottroadconstruction.com for additional project information.

City of Prescott • Public Works Dept. • 433 North Virginia Street • Prescott, Arizona 86301