

**Prescott Regional Airport  
Security Upgrades**

**DIBBLE**



**NOTICE OF INVITATION OF BID  
PRC Security Upgrades  
City of Prescott Project No. 21603  
ADOT Project No. E1S1M01C  
ADDENDUM No. 2  
November 3, 2021**

TO ALL PROSPECTIVE OFFERORS RESPONDING TO INVITATION FOR BID FOR CONSTRUCTION OF **PRC Security Upgrades** project at the PRESCOTT REGIONAL AIRPORT, as outlined in the aforementioned Invitation of Bids published on October 17<sup>th</sup> and October 24<sup>th</sup>, 2021 in the Prescott Courier; and available via the internet at <http://www.prescott-az.gov/business-development/purchasing/bid-listings/>.

**I. General**

1. All Bidders are reminded that all Addenda are required to be acknowledged within their bid proposal at the time bids are due or the bid can be considered non-responsive. Acknowledgment is located in Division I, Section 11 on page B-14.

**II. Changes to Contract Documents**

1. None.

**III. Changes to Construction Plans**

1. Drawing C3.2, Sheet 36, Fencing & Miscellaneous Details: Detail 1  
**Delete** Note 2

**IV. Contractors Questions and Responses**

1. **Question:** The manufacturer recommends clipping the spikes when you hit an obstruction that prevents you from pounding them in completely. This recommendation includes rocks and even hard clay (as they said, the animals are not going to dig through it after all). Note 2 on dwg C3.2 states that the contractor should excavate and backfill (see attached) when the ground is too hard for the spikes to penetrate. There is also a notation on the drawing to clip spikes at obstruction pointing at the concrete around a fence post. Please clarify if we can clip spikes only on the post concrete or at any obstruction such as cobbles, large rocks, caliche etc.

**Response:** Install the Wildlife Exclusion Fence Barrier according to the manufacturer's recommendations. Remove Note 2 directing the contractor to excavate. The contractor shall clip the spikes at any obstruction. The contractor shall ensure that the Wildlife Exclusion Fence Barrier is secure in its final position.